

Studwork, Gas & Power Specifications

Model: Mezzo Series
Vent: Vertical or Horizontal Termination
Capacity: Heats 100-140m² on high (Average)

See Installation Manual for Studwork Opening Requirements **(NOT BRICKWORK!)**

Other Requirements:

Gas: Provide a crimped/capped off copper gas line to suit 60mj and locate close to the bottom left hand side within the opening. Note: No composite pipe to be within same cavity.

Power: Provide a single non switch GPO/413 socket and locate close to the bottom right hand side within the opening and a power isolation switch to the face of the room wall.

Flue: Vertical Termination - 205mm diameter flue. Ensure a clear path is made available through to the roof space and that termination clearances are met. This is a gas regulation and cannot be overlooked.

Horizontal Termination – 205mm diameter flue. Ensure a clear path is made available through the wall and that termination clearances are met. This is a gas regulation and cannot be overlooked.

Access: Scaffolding is required for all multi storey installations or High/Steep single storey roof.

Room Vents: Not required for Balanced Flue fireplaces.