



## Studwork, Gas & Power Specifications

Model: 3X

Vent: Vertical or Horizontal Termination

Capacity: Heats 60-70 m2 on high (Average)

Finished Brickwork Opening Requirements (Exact):

Height: 800mm Note: Base to be solid and level, add height of hearth if applicable. The opening lintel can only be one brick in width.

Width: 880mm

Depth: 450mm (570mm max if rear vent)

Studwork Opening Requirements: refer to the installation manual and back of product brochure.

Other Requirements:

- Gas:** Provide a crimped/capped off copper gas line to suit 60mj and locate close to the bottom left hand side within the opening. Note: No composite pipe to be within same cavity.
- Power:** Provide a single non switch GPO/413 socket and locate close to the bottom right hand side within the opening and a power isolation switch to the face of the room wall.
- Flue:** Vertical Termination - 170mm diameter flue. Ensure a clear path is made available through to the roof space and that termination clearances are met. This is a gas regulation and cannot be overlooked.

Horizontal Termination – 205mm diameter flue. Ensure a clear path is made available through the wall and that termination clearances are met. This is a gas regulation and cannot be overlooked.

Access: Scaffolding is required for all multi storey installations.

Room Vents: Not required for Balanced Flue fireplaces.

277 Lord Street Perth, Western Australia 6000  
Telephone: (08) 9228 2600  
[www.fireplacecorner.com.au](http://www.fireplacecorner.com.au)  
ABN 18 095 891 740